



CHEVRON AUSTRALIA

TITLE: Demolition works - Beadon Creek Supply Base (EOI 29)

DESCRIPTION: Chevron Australia (Chevron) is seeking expressions of interest from potential vendors to undertake demolition works at the former Supply Base located on Beadon Creek Road, Onslow, Western Australia (the site).

Chevron are seeking to engage a contractor to undertake the isolation, demolition and disposal of onsite infrastructure (materials storage facility, wharf and landing facilities, fuel storage and dispensing facilities, and a communications tower) as well as earthworks during the restoration of the shoreline as required.

Contractor is to have proven capability and an ability to provide for or recruit locally within Onslow, Western Australia.

Contractor Capabilities and Requirements

The successful vendor will be required to provide the services or meet the requirements described below.

- Provide evidence of competency in the supervision and undertaking of demolition works as well as any relevant training, professional licences or certifications for staff (eg. electrical, plumbing, equipment operation);
- Have, or apply for and receive, a current demolition licence;
- Participate in a risk workshop and pre-start meeting with relevant stakeholders who have been engaged to provide environmental supervision during the works;
- Prepare a demolition plan consistent with the guidance provided in Safe Work Australia Demolition Work Code of Practice (Safe Work Australia, 2012), Australia Standards 2601-2001 The Demolition of Structures (Standards Australia, 2001). The demolition plan will be subject to review by Chevron prior to commencement of work;
- Secure development approval from the local government along with any other necessary permits;
- Isolation of services at the site including disconnection of electrical services and termination of water services at the meter;
- Demolition of all on-site infrastructure in accordance with site requirements, the approved demolition plan and the relevant code of practice;
- Excavation of potentially impacted or acid sulphate soils at the direction of the environmental supervisor;
- Storage, transport and disposal of waste material (including any impacted soils) at a Chevron approved facility;
- Source suitable clean fill material for the backfill of any on site excavations, site levelling and any earthworks required to restore the shoreline as required. Additional details around the volume and nature of fill required will be provided during the request for pricing;
- Supply and install geofabric, rip-rap, rock armour or other measures required for shoreline stabilisation. Note that Chevron will provide additional advice as to the nature of stabilisation measures during the request for pricing;
- Maintain and supply records of the nature, volume and disposal of all site derived wastes.

CONTACT: Industry Capability Network of Western Australia – www.icnwa.org.au/ContactUs.asp

Please Note: This is a request for specific expressions of interest. Service providers will be considered for inclusion in the RFP if suitably qualified against this package.

PROJECT URL: <https://australia.chevron.com/>

ATTACHMENT: N/A

CLOSING DATE: 6 March 2019