EXPRESSION OF INTEREST (EOI)

Project	CERES	
Company / Client	Perdaman Chemicals and Fertilisers Pty Ltd	
Package Material Requisition Number	0000-PA-E-87002	
Package Title	MATERIAL HANDLING - RECLAIMERS	
1. SUBMISSION PROCEDURE		
EOI Instructions	Supplier(s) are invited to express interest by registering on ICN Gateway where competency and previous positive experiences of similar supply of goods / services can be demonstrated.	
	When submitting interest registrants will be asked to complete an expression of interest document. The registrant's response will form their Expression of Interest (EOI) for material and/or services.	
	Suppliers will only be considered for Prequalification should they satisfy stated criteria, including but not limited to Health, Safety & Environmental Management, Quality management, financial standing, relevant experience and availability.	
EOI Closing Date	Please submit by close of business on 28/04/2023.	
Returnable Schedules	Where the EOI calls for any Returnable Schedules, please ensure all schedules are submitted.	
Contact	All initial enquiries should be made through the Industry Capability Network Western Australia (ICNWA). Ray Loh Ray.loh@icnwa.org.au	
	+61 (08) 9365 7499	
URL	For more information regarding the Perdaman, refer • https://www.perdamanindustries.com.au/scjv/	
2. INDICATIVE SCOPE OF WO	RK	

Package Description	Overview	
	Saipem Australia Pty Ltd and Clough Projects Australia Pty Ltd Joint Venture (herein referred to as the "CONTRACTOR") has reached an agreement with Perdaman Chemicals and Fertilisers Pty Ltd (herein referred to as the "OWNER") for the Engineering, Procurement, Construction and Commissioning of the PROJECT CERES located in Burrup Strategic Industrial Area, Burrup Peninsula, Western Australia.	
	Perdaman Chemicals and Fertilisers Pty Ltd (OWNER) is focused on the development of Perdaman - Project CERES which shall be the world's largest gas stream ammonia-urea plant with a production capacity of 2.14 MMTPA granular urea.	

General Scope of Supply / Services
Design, engineering, supply of materials, fabrication and assembly, shop tests and inspections, supply / prefabrication, assembly, painting and marking, packing, transportation, & Construction site services etc. of RECLAIMERS as detailed in ANNEXURE-1.
Design Capacity: Refer 1.3 of ANNEXURE-1 for Design Data summary
Responsibilities will include inter alia:
 Project management, reporting, attending meetings,
participation in risk assessment workshops.
 Comply with site mobilisation and site requirements.
Delivering work in a safe manner and to the required standards

Training and Site supervision assistance

Provide all equipment and materials for the Scope of Work

Standards	Compliance with National, International and Industry Standards, Australian and WA Regulatory requirements.	
Key Dates	Final Notice to Proceed planned during 2023	
Point of Delivery	Burrup Strategic Industrial Area (Western Australia)	
3. RETURNABLE DOCUMENTS		
List of Returnable Schedules List of experience on similar equipment supply projects		
4. DISCLAIMER		

This Expression of Interest to gain an insight into the capabilities of potential suppliers and/or service providers and not a Tender Invitation or offer - the schedule and content of this work is subject to change pending project demand and timelines.

ANNEXURE-1

Material Handling Reclaimer Package shall include but not limited to the following: VENDOR scope of supply shall include below main equipment's and any additional equipment and control system not listed, but which are considered necessary for safe and satisfactory operation shall be included in the VENDOR's scope of supply and identified accordingly.

MAIN EQUIPMENT LIST

VENDOR scope of supply shall include below main equipment's, but not limited to.

UNIT	TAG	DESCRIPTION	SERVICE	LOCATION
4120	4120-SR-001	Portal Scraper Reclaimer	Reclaiming from plant storage	Plant
4140	4140-SR-001	Portal Scraper Reclaimer	Reclaiming from port storage	Port

- Steel structures (design all Steel structures for equipment, transfer tower, galleries, trestles, truss, access platforms, as well fastening material (i.e. bolts, nuts, washers, etc.) Steel Structures, Ladders and Platforms in the reclaiming package.
- Reclaiming Equipment Portal Scraper & Rails for Reclaimers
- Electrical systems & components
- Instrumentation controls
- Other
 - Painting, Commissioning & Start-up Spares, packing, marking, preservation etc.
- Site supervision during erection, pre-commissioning, commissioning, start-up and site performance testing

Further inclusions consist of provision of management, design, calculation, procurement, fabrication, assembly, testing and certification to satisfy the scope of supply.

The following must be provided:

- Technical deviations list
- Special tools list
- Schedule of rates
- Spares list
- Quality assurance

1. DESIGN BASIS

1.1 UNIT DESCRIPTION

UNIT CODE	UNIT DESCRIPTION	
4120	Urea Storage and Reclaiming at Plant	
4140	Urea Storage and Reclaiming at Port	

1.2 EQUIPMENT DESCRIPTION

EQUIPMENT CODE	EQUIPMENT DESCRIPTION
CV	Belt Conveyor
TR	Tripper Car
SR	Portal Scraper Reclaimer

1.3 DESIGN DATA SUMMARY

UNIT 4120 - UREA STORAGE AND RECLAIMING AT PLANT			
STOCKPILE - COMPARTMENT	No.	1	
STOCKPILE CAPACITY	ton	75000	
HEIGHT OF STOCKPILE	m	16	
RECLAIMING EQUIPMENT	type	Double Boom Travelling Portal Scraper	
RECLAIMING CAPACITY	t/h	1100 (normal), 1210 (design)	
UNIT 4140 - UREA STORAGE AND RECLAIMING AT PORT			
STOCKPILE - COMPARTMENT	No.	1	
STOCKPILE CAPACITY	ton	65000	
HEIGHT OF STOCKPILE	m	16	
RECLAIMING EQUIPMENT	type	Double Boom Travelling Portal Scraper	
RECLAIMING CAPACITY	t/h	2200 (normal), 2420 (design)	