



## PLUTO LNG TRAIN 2

SR No.	Pending
Title	Removable Jacket
Work Description	<p>Removable jacketing work will be carried out per project specification 26221-100-3PS-NN00-00003 Rev.002. This work shall be carried out by specialized Subcontractor who will have the knowledge and experience in this kind of work. They are also required to have personnel experienced in measuring the actual components at field by touching or visualizing the items and to prepare a design drawing for manufacturing the blankets. Manufacturer shall be responsible for field measurement (Karratha Jobsite) by their design engineer and to prepare the drawings for the fabrication work.</p> <p>All relevant materials shall be identified based on the project specification and submitted to Bechtel engineering department for review and approval prior to purchase, including two (2) sample blankets to be fabricated and train fit before mass production, each item to be inspected in compliance with project specification prior to installation at permanent plant items.</p> <p>Items not in compliance shall be modified by manufacturer at cost and replaced. Bechtel have the right to visit the manufacturer facility at any time during the fabrication work for ongoing inspection and material verification.</p>
Schedule	Works to occur circa Q3 2024