



## PLUTO LNG TRAIN 2

SR No.	Pending
Title	Supply of High Pressure Nitrogen
Work Description	<p>Subcontractor is responsible for the supply of all materials and equipment required to support High Pressure (HP) leak testing of up to 150 barg and of liquid nitrogen converters capable of achieving the same pressure while providing high purity low moisture gaseous nitrogen.</p> <p>Subcontractor is responsible for providing all ancillary equipment including but not limited to pigs, hoses, whip-checks, instrumentation, overpressure protection systems compliant to Australian and industry standards to support connection to plant for provision of nitrogen.</p> <p>All equipment shall be certified for the duration of the site activities. Subcontractor to provide competent personnel to make piping connections and operate equipment on potentially on a 24/7 basis. The following works are excluded from Subcontractor Scope of Work: Supply of Cranes, Cranes Operator, Lifting Equipment and Rigging Crew.</p> <p>Supply of site transportation including trucking and forklifts/telehandlers. Crib and office facilities (including power and water connected to cribs and offices).</p>
Schedule:	Commencing circa Q3 2025 until circa Q1 2026.