



## PLUTO LNG TRAIN 2

Subcontract No.	C082
SR No.	E00Z-00001
Title	Pre-commissioning and Commissioning of Electrical & Instrumentation Services
Work Description	<p>Subcontractor is responsible for Subcontractor is responsible for the supply of all testing equipment required to support testing and commissioning of:-</p> <p>33kV/6.6kV/690V/400V Schneider Switchboards and 11/33kV 50MVA Transformer, 33kV/6.6kV 25MVA/16MVA/12.5MVA Transformers, 6.6kV/690V 2.5MVA/2MVA Transformers, 6.6kV/420V 2MVA/1.6MVA/1.25MVA/1MVA Transformers.</p> <p>Subcontractor is responsible for providing all testing equipment including but not limited to Hipot Tester, Megger, Omicron CMC 356/ CPC100, 24VDC Power Supply units, 110V Power Supply Units etc.</p> <p>All equipment shall be calibrated for the duration of the Site activities. Subcontractor to provide competent personnels to test protection relays, Current Transformers, Scheme function checks etc and operate Original Equipment Manufacturer equipment.</p> <p>The following works are excluded from Subcontractor scope of work: Relay setting files will be free issued to the Subcontractor.</p> <p>Crib and office facilities (including power and water connected to cribs and offices).</p>
Schedule:	Commencing circa Q4 2024 until circa Q3 2025.